BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZO

Executive Engin
Byatarayanapura D
B.B.M.P., Bangalo

DRAFT TENDER SCHEDULE

Issued to :

Original / Dupli
Item No.

Name of the Work : emoval of Debris and Berm Cutting in Doddabommasandra area
10 (Doddabommasandra), Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	
1	1244.25	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	75.60	
2	1422.00	Earth work in surface excavation in **ordinary soil** for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed etc complete as per specifications and directions of engineer in charge of the work	Cum	146.88	
3	2666.25	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc complete as per specifications and directions of engineer in charge of the work	Cum	73.57	

Signture of the Contractor

Executive Engi
Byatarayanapura D
BBMP, Bangalore

ಕರಮು ಟೆಂಡರ್ ಷರತ್ತುಗಳಿಗೆ
ಶಿದ್ಧವಹಿಗಳ ಸಂಖ್ಯೆ.....
ಶಿದ್ಧಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

Superintending Engineer
Yelahanka Zone
BBMP, Bangalore